BRUHAT BANGALORE MAHANAGARA PALIKE

Dasarahalli Zone

Office of the Exexutive Engineer Project Division (Dasarahalli)

Modified Schedule-B

Name of The Work :- Improvements to Ashwathakatte near Muthuraya Swamy temple Mallasandra ward no.13 Shettyhalli Sub Division

Name of The Contractor :- Sri. Puttaraju A

Sl No	Description of work	Unit	Qty	Sanctioned Rate	
				in Figures (Rs.)	In Words(Rs.)
1	Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum.	76.34	405.64	Rupees Four Hundered Five and Thirty Four Paise only
2	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum.	32.55	5449.68	Rupees Five Thousand Four Hundred Forty Nine and Sixty Eight Paise only
3	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, ,pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications.	Cum.	26.41	6718.68	Rupees Six Thousand Seven Hundred Eighteen and Sixty Eight Paise only

Scanned with CamScanner

4	Filling Available excavated earth(excluding rock) inside cum of foundation upto plinth in layers not exceeding 20cm in depth compacting each deposited layer by ramming after watering with lead upto 50mtr and lift upto 1.5mtr including cost of all labour etc complete as per specification. specificatrion	Sqm	36.15	137.16	Rupees Three Hundred Thirty Seven and Paise One Six Only
5	KSRRB : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1 :6, and edges of stones chistle dressed in courses not less than 15cms high, bond stones at twom. Apart in each course including cost of all materials,labour,curing complete as per specifications.KBS 5.1.13(Page No. 23,It No.5.9 of KPWD S.R 2016-17)	Cum	1.04	5405.40	Rupees Five Thousand Four Hundred Five and Forty Paise Only
6	Providing and Laying in position reinforced cement concrete of design mix M20 with OPC cement @ 300Kgs with 20mm and down size graded granite metal course aggregate @ 0.64cum and fine aggregate @ 0.43cum, with superplastisiser @ 3ltr confirming to IS 9103-1999 Reaffirming 2008, machine mixed, concrete laid in layers not exceeding 15cms thick,well compacted in foundations plinth and cills including cost of all materials, Labours, HOM of Machineries, curing complete as per specification	Cum	1.38	5985.36	Rupees Five Thousand Nine Hundred Eighty five and Paise Thirty Six Only
7	Providing and Removing centering and shuttering, strutting proping etc. and removal of form work for foundations footings bases of columns for mass concrete including cost of all materials labour complete as per specifications. Specification	Sqm	91.84	249.48	Rupees Two Hundred Fourty Nine and Paise Fourty Eight Only

Scanned with CamScanner

8	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3, TMT bars Fe 500. Page No. 17/ Item No. 4.46.2/ PWD SR 2016-17	Tonnes	2.11	65455.96	Rupees Sixty Five Thousand Four Hundred Fifty Five and Paise Ninety Six Only
9	Providing and Fixing for flooring 20mm thick gang saw water cut sadarahalli gray granite in CM 1:4 propotion, cut to required shape, pattern with paper joints, finished with cement mortor using white cement and colour pigments to match the colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of curring - Minimum width of 1200mm.,complete as per specification.KSRB 14.61.1	Cum	88.00	1984.00	Rupees One Thousand Nine Hundred Eighty Four Only.
10	Providing and fixing 304 grade stainless steel hand rails of 14 guage pipes for Ramps staircase made out of stainless steel hollow piupes using 50 mm dia for verticals@ 1.60 mts c/c fixed to the ramps or steps by drilling with bolts and 100mm dia M S base plates 10mm guage for fixing of vertical pipes 4 Nos ancher bolts& 40 mm dia pipes fixed horizontally for 2 rows top one pipe fixed with vertical pipes another one fdixed with elbows and 25 mm dia pipes are fixed horizontally for 2 rows below top measure @ equal intervels including cutting welding bending wherever necessary with suitable caps @ tops bottoms & corners finishinconveyance of all materials labour for all items of work HOM oftransportation chacomplete as per specification and direction of the Engineer incharge of the work	Sqm	25.37	6286.68	Rupees Six Thousand Two Hundred Eight Six and Paise Six Eight Only

Scanned with CamScanner

11	Providing full nosing for 20mm thick granite slab using required machinary including cost and conveyance of all materials; labour for all items of works H O M of equipment etc; complete as per specification	M	31.01	257.04	Rupees Two Hundred Fifty Seven and Paise Zero Four Only
12	KSRB 6-5.3;Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size and class designation 5.0 Newton per sq mm (table moulded) with cement morter 1;6 for basement and super structure including cost of materials, labour, HOM of machinary, curing complete as per the direction of the Engineer incharge of the work	Sqm	5.23	6935.58	Rupees Six Thousand Nine Hundred Thirty Five and Paise Fifty Eight Only
13	Providing 18mm thick cement plaster in single coat with cement morter 1;4 to burnt brick masonry including off corners wherever required smooth rendering Providing and removing scaffolding including cost of materials, labour, HOM of machinary, curing complete as per specification	Sqm	21.16	169.00	Rupees One Hundred Sixty Nine Only
14	Providing And Constructing Mantapa using Sadarahallli Granite stones of size of 0.40x0.40x2.3 measurment for four numbers pillers and four numbers of beams of size 0.20x0.30x2.75 mtr and with granite slab roof of 4.30mtrx3.00mtrx0.15thick including cost of all loading and unloading and the lead for bringing the stone to the workspot including cost of all carving work dressing polishing and pinishing and insatalling at woork site etc.. complete	No	1.00	437441.07	Rupees Four Lackh Thirty Three Thousand Four Hundred Fourty One and Paise Zero Seven Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Scanned with CamScanner